

Annexure - 1

Construction/supply & Installation of different civil works at different sites.

Sl. No	Item of work	Qty	Unit	Quoted Rate (Rs.) (In Figure)	Quoted Rate (Rs.) (In Word)
1	Supply & fixing of inugration board 2.5ft x 3ft, (Granite Base)	1	Nos.		
2	Supply and fixing of shed work in open area including masquito net and poly carbonate sheet (18' x 15')	1	job		
3	UNIT-1 :- Providing & making storage type unit of approx. size 5000mm(L) X 600mm(W) X 2400mm(H) as shown in design or as per approved working drawing made up of 18mm/12mm thick ply of make Century ply or Green ply or Equivalent , Finished with 1mm thick laminate on exposed surface & 0.8 mm thick laminet on inner surface make Century laminate or Green laminate or equivalent. used artificial grass sheet & logo shown in design, use 0.8mm thick MDF design at front of unit with paint finish. (includes all necessary hardware)	1	Nos.		
4	Providing and fixing DGVT wall tiles of size 600mmX600mm conforming to IS : 15622 of approved make as approved by Engineer-in-charge in skirting , risers of steps and dados over 12 mm thick bed of cement Motar 1:3(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	1	sqm.		
5	Providing and laying wood like plank floor tiles of size 196mmX1200mm {thickness to be specified by the manufactruer) with water absorption's less than 0.08 %and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete.	1	sqm.		
6	Brass Aldrops of 300mm long and 16mm dia with required screws, bolts and nuts	1	each		
7	Providing and fixing D type Stainless steel Handle of size 250 mm including all fittings	1	each		
8	Stainless steel Aldrops of 300mm long and 16mm dia with required screws, bolts and nuts	1	each		
9	Providing and fixing bright finished SS 125 mm mortice latch with one dead bolt of approved quality with necessary screws etc. complete	1	each		
10	Providing and fixing stainless steel tower bolts of size300x10mm, ISI marked, with necessary screws etc. complete:	1	each		
11	Providing and fixing stainless steel tower bolts of size250x10mm, ISI marked, with necessary screws etc. complete:	1	each		
12	Providing and fixing stainless steel sliding door bolts of size125x10mm, ISI marked, with necessary screws etc. complete:	1	each		
13	Providing and fixing stainless steel wall mount hanger with three hooks of length 150mm ISI marked, with necessary screws etc. complete:	1	each		

Sl. No	Item of work	Qty	Unit	Quoted Rate (Rs.) (In Figure)	Quoted Rate (Rs.) (In Word)
14	Providing and fixing bright finished SS Indicator bolt baby latch for changing rooms of approved quality with necessary screws etc. complete	1	each		
15	Providing and fixing 5mm thick mirror of superior glass (of approved quality) in required size Make: Saint Gobain, ModiGuard	1	sqm.		
16	Providing and fixing H type Stainless steel Handle of size 900 mm including all fittings	1	Each		
17	32mm Dia HT Bolts minimum length 600mm straight, thread 80mm with washer and two nos. nut. (Shape J-type, over all length 700mm)	1	nos.		
18	Chemical Fastener of dia 20mm and length 260mm Make: Fischer	1	nos.		
19	Beam fabricated with moulded steel plates of thickness 6mm, welded to bottom & top MS plates, further welded to hold in position with steel battens at three different positions (2 sides & 1 center). Fixing in position by welded connection with all necessary tools & tachles including priming coat.	1	Kg		
20	SUPPLY AND INSTALLATION OF GANDHI MURTI (TECHNICAL DETAILS) MATERIAL TO BE USED FIBER REINFORCED POLYMER, HEIGHT OF THE STATUE (TOP- BOTTOM)- 5'-4"	1	Nos.		
21	SUPPLY AND INSTALLATION OF ROUND WHEEL CHARKHA (TECHNICAL DETAILS) ONE SPINNING WHEEL WITH WOOD POLISH ON EXPOSED SURFACE . (1500 (D) X 2400 (H) X 300 (L)	1	Nos.		
22	SUPPLY AND INSTALLATION OF FLOWER POT WITH NATURAL PLANT HAVING BASE PLATE (TECHNICAL DETAILS) POTTED PLANT 18 INCH PVC CONTAINERS.	1	NOS.		
23	SUPPLY AND INSTALLATION OF natural GRASS at required place/area	1	SQM		
24	SUPPLY AND INSTALLATION OF WOODEN HANGER WITH BIHAR KHADI LOGO AND WOOD POLISH HOOK MATERIALS -SS HOOK TYPE – C HOOK.	1	Nos.		
25	SUPPLY AND INSTALLATION OF MANNEQUINS (TECHNICAL DETAILS) MATERIAL – FIBER GLASS LOCKS – STAINLESS STEEL LOCK BASE PLATE – CHROME, STAINLESS STEEL COLOUR – WHITE MALE,FEMALE,CHILD of standard size POSTURE – MAINLY STRAIGHT COLOUR – MATT.	1	Nos.		
26	SUPPLY AND INSTALLATION OF SENSOR GATE (TECHNICAL DETAILS) 12 FEET RAIL XLC – 4200 AUTOMATIC SIDLING XLC – 8006 G/W/ BRACKET XLC – 8028 SOFTWARE. MAKE – DORMA.	1	Nos.		

Sl. No	Item of work	Qty	Unit	Quoted Rate (Rs.) (In Figure)	Quoted Rate (Rs.) (In Word)
27	SUPPLY AND INSTALLATION OF SHOPPING TROLLEY DIMENSION (MM) – 350(B) X 500(L) X 970MM (H) WEIGHT – 15 KG CAPCITY OR 100 LTR COLOUR – SS CHORME, HAVING 100 MM PU BLACK WHEELS. MAKE-sigma or equivalent.	1	Nos.		
28	SUPPLY AND INSTALLATION OF Q UP STAND (TECHNICAL DETAILS) BELT SIZE-7MTR POLE SIZE-37X2.5 INCH POLE THICNESS-1MM BASE SIZE-12 INCH DIA CURVE WITH DOUBLE EMBOSSING MATERIAL-SS 202 GRADE WIGHT-7KG STRAP COLOUR-RED,YELLOW,BLUE AND BLACK.	1	Nos.		
29	SUPPLY AND INSTALLATION OF DOOR MAT IN STANDARD DOOR SIZE.	1	Nos.		
30	SUPPLY AND INSTALLATION OF LUGGAGE TOKEN (TECHNICAL DETAILS) 3 MM ACRYLIC LASER ENGRAVED TOKEN.	1	Nos.		
31	SUPPLY AND INSTALLATION OF WALL PAPER HAVING THICKNESS OF 0.8MM as per direction of Engg in charge.	1	SQM		
32	SUPPLY AND FIXING OF 25 MM THICK granite stone INAUGURATION BOARD WITH ENGRAVED LOGO AND LETTERS. (size-900x1200MM).	1	Nos.		
33	SUPPLY AND FIXING OF GANDHI THOUGHTS IN GOLDEN ACRYLIC LETTER WITH ACRYLIC BASE PLATE size 780x970mm.	1	Nos.		
34	Anchoring bolt for staircase 20x300mm with required anchoring chemical make-WUERTH.	1	Nos.		
35	Anchoring bolt for staircase 20x400mm with required anchoring chemical,make-WUERTH.	1	Nos.		
36	Removal of fully grown plants/trees from the historic/old and monuments by using both physical and chemical method.physical method includes cutting them with suitable sharp cutting instrument and chemical method includes stem controlled by using herbiside.like-glyphosate,paraquat,disodium salt,alrazine or 1%solution of sodium arsnate or arsnite injected in stem of plats.	1	Nos.		
37	core cutting for existing slab for rain water pipe and fire fighting 150mm.	1	Nos.		
38	core cutting for existing slab for rain water pipe and fire fighting 200mm.	1	Nos.		
39	core cutting for existing slab for rain water pipe and fire fighting 250mm.	1	Nos.		
40	SUPPLY AND FIXING OF GRANITE BASE WITH 1 INCH SS GOLDEN LETTERS FOR GANDHI THOUGHTS FRAMED WITH WOODEN FRAMING(size 700x950mm).	1	Nos.		
41	Providing and Fixing ACRYLIC LETTER SIGNAGE IN DIFFRENT SIZES OF LETTERS.	1	SQ INCH		

Sl. No	Item of work	Qty	Unit	Quoted Rate (Rs.) (In Figure)	Quoted Rate (Rs.) (In Word)
42	Providing and laying vitrified floor tiles in different sizes {thickness to be specified by the manufactruer) with water absorption's less than 0.08 % and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand including grouting the joint with white cement and matching pigments etc., complete. Size of Tile 60x120 cm (SOMANY)	1	SQM		
43	Supply and installation of Standard quality of Stainless steel letter, all complete as per approved drawing, design and size. S.S. letter size- 300mm	1	Each		