



आधारभूत संरचना विकास प्राधिकार

(बिहार सरकार का एक उपक्रम)

प्रथम तल, उद्योग भवन, पूर्वी गाँधी मैदान, पटना।

Email-md@idabihar.com , Web-www.idabihar.com, phone: 0612-2675933, 2675935, Fax no-2675934

Corrigendum No.II

Sub: Construction of Precast storm water drainage at Industrial Growth centre
Marnga, Purnea.

Tender No. NIT - 73/TEN/IDA/22

This is to inform all bidders that for Drain Size 450mm ,900mm,1200mm,1500mm,2000 mm or any drain size used for serial no 10 - M-30 should be read/quoted for instead for M-25 :

Sl. No.	For drain size	Tender item uploaded	Tender item to be read/quoted as
10	Size 450mm ,900mm,1200mm,1500mm,2000 mm or any drain size used	Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete structural elements, excluding the cost of centring, shuttering finishing and reinforcement, M-25 grade reinforced cement concrete to precast drains made at factory or near site in campus if place provided by BIADA , including hosting and installing to the site where precast drains are to be fixed/installed , including all the cost of transportation from factory or yard .If required some parts may have to be casted at site for diiferent conditions like crossing, silting pit , positions near water bodies etc (For pre cast drains the drain shall have grooves for jointing at the edge, curing arrangements, special in built insert, sleeves/hooks at appropriate location as specified in drawing for fixing, lifting including mechanical means, loading, transportation at site including all leads, lifts. All joints to be specified joint filling compound material.)	Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete structural elements, excluding the cost of centring, shuttering finishing and reinforcement, M-30 grade reinforced cement concrete to precast drains made at factory or near site in campus if place provided by BIADA , including hosting and installing to the site where precast drains are to be fixed/installed , including all the cost of transportation from factory or yard .If required some parts may have to be casted at site for diiferent conditions like crossing, silting pit , positions near water bodies etc (For pre cast drains the drain shall have grooves for jointing at the edge, curing arrangements, special in built insert, sleeves/hooks at appropriate location as specified in drawing for fixing, lifting including mechanical means, loading, transportation at site including all leads, lifts. All joints to be specified joint filling compound material.)

शेष अन्य शर्तें यथावत् रहेगी।

विश्वासभाजन

ह0 / -

कार्यपालक अभियंता (पी0डी0ए0)

ज्ञापांक:- 3980/PDA

दिनांक:- 17-11-2022

प्रतिलिपि: 1. सूचना पट्ट पर प्रकाशन हेतु जनसम्पर्क पदाधिकारी को आवश्यक कार्रवाई हेतु प्रेषित।

2. वेबसाईट पर प्रकाशन हेतु कम्प्यूटर प्रोग्रामर को आवश्यक कार्रवाई हेतु प्रेषित।

3. eproc वेबसाईट पर प्रकाशन हेतु Junior Engineer (Tech), Shri Mukesh Kumar, को आवश्यक कार्रवाई हेतु प्रेषित।

कार्यपालक अभियंता (पी0डी0ए0)